The Vertical Solutions Company Rail Bracket Inserts

INW04 - Drywall or Steel Construction

INM05 - Masonry

Drywall / Wood Construction

- 1. Find the installation locations per the attached diagram and the local Construction Superintendent.
- 2. Verify that headers are installed in the insert locations.
- 3. Drill through the header and attach the insert with three (3) 5/8" bolts with flat and lock washers on the rear of the header. (Lag bolts are not an accepted means for attaching these inserts.)
- 4. Attach and finish 2 layers of 5/8" drywall being sure that the insert is grouted completely.

Steel Construction

- 1. Find the installation locations per the attached diagram and the local Construction Superintendent.
- 2. Stitch weld the insert to the structure in at least five (5) equally spaced locations both top and bottom.

Masonry Block Construction

- 1. Find the installation locations per the attached diagram and the local Construction Superintendent.
- 2. Make a 1 1/4" notch in the top edge of the block to fit the insert.
- 3. Install the insert flush with the face of the block and slush fill the blocks around the insert legs.
- 4. Lay the next course of block and slush fill that as well.
- 5. Grout solid all around the insert.

Attach the rail brackets to the inserts using standard 5/8" bolts, washers and nuts; no special insert washers are required.


These inserts are to be used as required by local codes and regulations. In straight line pull-out tests the minimum failure force is 5,800 pounds, well in excess of most code requirements. Check with local authorities to ensure code compliance.

For more information contact:




Test Bolt Position	Minimum Failure Force
Inside End of Slot	7220 lbs.
Outside End of Slot	6690 lbs.
Center of Slot	5800 lbs.

Insert Installation Detail



sales@verticalsolutionscompany.com

Insert/Rail Fastening Locations



Hoistway Front View

Hoistway Side View

Divider Beam/Insert spacing shown above is typical. Verify with the local Construction Superintendent that this spacing is correct.

